



# higher education & training

Department:  
Higher Education and Training  
REPUBLIC OF SOUTH AFRICA

Ingwe TVET College



Enquiries: A. Madukuda

Tel: 039 940 2142

Ext 171

## RE- ADVERT

BID DESCRIPTION	BID NO	CLOSING DATE	ENQUIRIES
CONSTRUCTION OF AN ACCESS ROAD AT ADMIN CENTRE.	INGWE/031/2025	DATE: 07/03/2025	TECHNICAL: MR. O. HANISE TEL: 039 940 2142 SCM: MS. A. MADUKUDA TEL: 039 940 2142

Kindly furnish me with a written quotation for the provision of services as detailed in the enclosed specification. The quotations must be submitted on the letterhead of your business or have your business stamp. Quotations are to be placed in a sealed envelope endorsed "bid number and description" must be deposited in the tender box situated at the reception area not later than 12H00pm on Wednesday the 07<sup>th</sup> March 2025 at Ingwe TVET College, Mount Frere Administration Offices at the reception area.

### THE FOLLOWING MANDATORY DOCUMENTS MUST BE SUBMITTED WITH THE QUOTATION AND FAILURE TO SUBMIT WILL LEAD TO THE BIDS BEING DECLARED NON-RESPONSIVE:

- Price(s) quoted must be valid for at least thirty (30) days from date of your offer.
- Price(s) quoted must be firm and must be inclusive of VAT.
- Firm Delivery Period must be indicated.
- A valid SARS TAX Compliance status with PIN.
- Updated CSD (Central Supplier Database) report.
- Company municipal statement of account not older than three (3) months or company lease agreement if renting premises or affidavit from SAPS stating that the company is not obliged to pay municipal rates or ward council letter confirming the proof of address for the company for non – rates paying areas or rural areas.
- **Valid CIDB grading ICE or higher**
- Joint Ventures to attach: JV Agreement and letter of Signatory.
- **Completed SBD 4 – as per PFMA SCM Instruction No. 03 of 2021/22 effective from 1 April 2022, the revised SBD 4 must be fully completed and signed. SBD 8&9 are repealed (no longer required). Failure to submit as instructed will lead to the bids being declared non – responsive. Bidders must download the revised SBD 4 from the College website or National Treasury website.**

### BIDDERS SHOULD TAKE NOTE OF THE FOLLOWING BID CONDITIONS:

- Ingwe TVET College Supply Chain Management Policy will apply.
- 80/20 preferential procurement point system will be applied.
- Ingwe TVET College does not bind itself to accept the lowest bid or any other bid and reserves the right to accept the whole or part of the bid.
- Bids which are late, sent via e-mail, incomplete, and unsigned, will not be accepted.
- No quotations will be considered from persons in the service of the state.
- Failure to comply with these conditions will invalidate your offer.

Central Office  
Badibanise Village  
Mount Frere  
Tel: 039 940 2142

Mount Frere Campus  
Cancele Road  
Mount Frere  
Tel: 039 940 2142 ext.200

Ngqungqushu Campus  
Magwa Road  
Lusikisiki  
Tel: 039 940 2142 ext.300

Sitoto Campus  
Mhlanga Village  
Bizana  
Tel: 039 940 2142 ext.400

Maluti Campus  
Mli Road  
Maluti  
Tel: 039 940 2142 ext.500

Mt Fletcher Campus  
Hospital Area  
Mount Fletcher  
Tel: 039 940 2142 ext.600

[www.ingwecollege.edu.za](http://www.ingwecollege.edu.za)





# higher education & training

Department:  
Higher Education and Training  
REPUBLIC OF SOUTH AFRICA

Ingwe TVET College



Skill the nation and let everyone prosper

PO Box 92491 Mt Frere 5090

Enquiries: Otto Hanise

Email: mhanise@ingwecollege.edu.za

Tel: 039 940 2142

## PAVING OF STREET AT INGWE ADMINISTRATION CENTRE (100m)

### BILL OF QUANTITIES

Item No

Description

Unit

Qty.

Rate

Amount

### New Works

NOTE: Tenderers are advised to study the Model preambles for trades before pricing this bill.

This is not a Lump - sum tender. Tenderers shall allow opposite each item for any cost involved with such item.

where products or services are rendered free of charge, in such instance the rate or price should be indicated as R0.00

A Fully completed and priced tender document must be handed in with tender closing.

All Quantities will be re measured and checked on completion for final account purposes.

All sizes given must be verified and confirmed on site prior to installation.

### PRELIMINARIES AND GENERAL ITEMS

A	Management, Supervision and programming of works	Item	1		
B	Plant, Equipment, Sheds, and Offices, etc.	Item	1		
C	Ablution Facilities for workers	Item	1		
D	Works cleaning and clearing	Item	1		
E	Health and Safety	Item	1		
F	Standing time	Hr	8		
G	The Contractor shall provide an adequate water supply for the works at his own expense including necessary temporary plumbing.	Item	1		

Specification of Paving a street at – Ingwe Administration Centre

H The Contractor shall provide an adequate electrical supply for the works at his own expense including necessary temporary Installation work.

Total Carried Forward

R

**PAVING OF STREET AT INGWE  
ADMINISTRATION CENTRE (100 m)**

REMOVALS

A	Take up and remove from Site the Existing cement blocks for walkways, pack them within the Site in dedicated point.	m2	113
B	Dig up and remove the Internet and power cable that connects the two buildings, so that they are visible and for them not to be damaged.	Item	1
C	Allow the budgetary amount of R3 000.00 (Three Thousand Rand) for Blocking off the sewerage and water line, and reconnect later on.	Item	1

EARTHWORKS (PROVISIONAL)

D	Open Face excavation in earth to reduce level to final level under paving, etc.	m3	500
E	Extra over excavations for carting away surplus material from excavations to a municipal dumping site located by the contractor in all related charges.	m3	500
F	Scarify in-situ material to a depth of 100mm and compact to 93% Modified AASHTO Density	m2	1650
G	Class G5 sub-base earth filling (150mm thick) shaped to falls and cross falls under pavers and compacted to 95% Modified AASHTO density.	m3	390
H	20mm Thick, clean river sand bed under pavers	m2	500
I	Prescribed "Modified AASHTO Density" test on filling	No	2

SOIL POISONING

J	Soil Insecticide under paving including forming and poisoning shallow furrows against foundations walls, etc. Filling in furrows and ramming	m2	500
---	--	----	-----

**CONCRETE**

K 15 Mpa / 19mm Unreinforced concrete in surface blinding for kerbing (Foundations)

m3 20

**MOVEMENT JOINTS**

L Form expansion joints with 10mm thick Jointex between vertical concrete and paving brick surfaces not exceeding 300mm high.

m 200

Total Carried Forward

**PAVING OF STREET AT INGWE ADMINISTRATION CENTRE (100m)**

R

**SABS KERBS AND PAVING**

A Supply, Deliver and Lay 80mm thick Type SA Interlocking Concrete Paving blocks to SANS 1058 (This includes laying of 20mm sand bed, grouting and cutting where necessary)

M2 500

Preparation and laying of kerbs to SANS 927 (This Includes Excavating backfilling behind the kerb and grouting)

B Figure 4 Kerbs

m 220

C Centre Line Marking using road marking paint.

m 100

D Cleaning of Site and disposal of rubble Material

Sum 1

Total Carried forward

R



**PAVING OF STREET AT INGWE  
ADMINISTRATION CENTRE (100 M)**

**SUMMARY**

Section	Description				Amount
1.	Preliminaries & General Items				
2.	Removals, Earthworks, Soil poisoning, Concrete, Movement Joints				
3.	Kerbs & Paving				
	Sub-total				
	Vat @ 15%				R
	Total				R
	Amount carried to form of offer				R

Compiled by:



.....  
Otto Hanise  
AD: Facilities & Maintenance  
Date: 10/02/2025